ABBREVIATIONS

ABV	ABOVE
AD	ACCESS DOOR
ADR	AREA DRAIN
AFF	ABOVE FINISHED FLOOR
AFH	ANTIFREEZE HYDRANT
AFS	AUTOMATIC FLUSH SYSTEM
AP	ACCESS PANEL
APPROX	APPROXIMATE
AV	ACID VENT
AVG	AVERAGE
AVTR	ACID VENT THRU ROOF
AW	ACID WASTE
AWS	ANIMAL WATERING SYSTEM
BA	BREATHING AIR
BCA	BOTTLED COMPRESSED AIR
BFF	BELOW FINISHED FLOOR
BFP	BACKFLOW PREVENTOR
BG	BELOW GRADE
BHP	BRAKE OR BOILER HORSEPOWER
BIW	BIO-WASTE
BIWV	BIO-WASTE VENT
BLDG	BUILDING
BLW	BELOW
BOP	BOTTOM OF PIPE
BOT	BOTTOM
BSC	BASEMENT SPILL CONTAINMENT
BTU	BRITISH THERMAL UNIT
°C	DEGREES CENTIGRADE
℄	CENTER LINE
CAP	CAPACITY
CB	CATCH BASIN
CD	CLEAN DRAIN
CDV	CLEAN DRAIN VENT
CFD	COVERED FLOOR DRAIN
CFH	CUBIC FEET PER HOUR
CFM	CUBIC FEET PER MINUTE
CGM	COMPRESSED GAS MANIFOLD
CI	CAST IRON
CLG	CEILING
CLS	CLEAN STEAM
CM	CONSTRUCTION MANAGER
CMS	CENTRAL MONITORING SYSTEM
CO	CLEANOUT
CO_2	CARBON DIOXIDE
COL	COLUMN
COMP	COMPRESSOR
CONC	CONCRETE
COND	CONDENSATE
CONN	CONNECTION
CONT'N	CONTINUATION
CONTR	CONTRACTOR
CP	CONCRETE PIPE
CS	CUP SINK
D	EQUIPMENT DRAIN
DCW	DOMESTIC COLD WATER
DO	DESICCANT AIR DRYER
D-SP	DRY SPRINKLER MAIN
DEPT	DEPARTMENT
DF	DRINKING FOUNTAIN
DFU	DRAINAGE FIXTURE UNIT
DHWS	DOMESTIC HOT WATER SUPPLY
DHWR	DOMESTIC HOT WATER RETURN
DIA	DIAMETER
DIE	DROP IN ENCLOSURE
DIFF	DIFFERENTIAL
DISCH	DISCHARGE
DIV	DIVISION
DIW	DOWN IN WALL
DN	DOWN
DS	DRY STANDPIPE
DTWR	DOMESTIC TEMPERED WATER RETURN
DTWS	DOMESTIC TEMPERED WATER SUPPLY
DWG	DRAWING
DWV	DRAINAGE, WASTE & VENT
(E)	EXISTING
EA	EACH
EDI	ELECTRODEIONIZATION
EDR	ELECTRODIALYSIS REVERSAL
EG	FOR EXAMPLE
EL	ELEVATION OR EXPANSION LOOP
ELEV	ELEVATOR
ENT	ENTERING
EQ	EQUAL
EQUIP	EQUIPMENT
EQUIV	EQUIVALENT
ET	ELECTRICALLY TRACED PIPING
ETC	AND SO FORTH
EWT	ENTERING WATER TEMPERATURE
EWC	ELECTRIC WATER COOLER
EXT	EXTERNAL
EW	EYEWASH/SAFETY SHOWER
EWH	ELECTRIC WATER HEATER

F	FILTER
°F	DEGREES FAHRENHEIT
FA	FROM ABOVE
FB	FROM BELOW
FCO	FLOOR CLEANOUT
FD	FLOOR DRAIN
FDC	FIRE DEPARTMENT CONNECTION
FDV	FIRE DEPARTMENT VALVE
FDVC	FIRE DEPT VALVE AND CABINET
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER CABINET
FF	FINISHED FLOOR
FI	MULTIMEDIA FILTER
FIC	CARBON FILTER
FIN	FINISHED
FL	FILL LINE
FLEX	FLEXIBLE
FLR	FLOOR
FP	FIRE PROTECTION
FPM	FEET PER MINUTE
FPS	FEET PER SECOND
FR	FROM
FS	FLOW SWITCH
FT	FEET
FTB	FLOOR TO BOTTOM
FTC	FLOOR TO CENTERLINE
FW	FLUSH WATER
FWE	FURNISH WITH EQUIPMENT
FXC	FLEXIBLE CONNECTION
G	GUIDE (S)
GA	GAUGE
GAL	GALLON
GALV	GALVANIZED
GB	GAS BOOSTER
GC	GENERAL CONTRACTOR
GMP	GOOD MANUFACTURING PRACTICE
GPD	GALLONS PER DAY
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
GPR	GAS PRESSURE REGULATOR
GWH	GAS WATER HEATER
H_2O	WATER
HB	HOSE BIBB
HBD	HUB DRAIN
HCV	HOUSECLEANING VACUUM SYSTEM
HX	HEAT EXCHANGER
HD	HEAD
HP	HORSE POWER
HPC	HIGH PRESSURE CONDENSATE
HPS	HIGH PRESSURE STEAM
HR	HOUR
HS	HOSE STATION
HTR	HEATER
HT	HEIGHT
HWG	HOT WATER GENERATOR
ID	INTERNAL DIAMETER
IE	INVERT ELEVATION
IN	INCHES
INCL	INCLUDING
INT	INTERNAL
INV	INVERT
KW	KILOWATT
LAB	LABORATORY
LAV	LAVATORY
LB	POUND
LIQ	LIQUID
LO	LOCKED OPEN
LS	LAB SINK OR LOCK SHIELD
LVG	LEAVING
LW	LAB WASTE
LWT	LEAVING WATER TEMPERATURE
MAV	MANUAL AIR VENT
MAX	MAXIMUM
MBH	THOUSAND BTU'S PER HOUR
MC	MECHANICAL CONTRACTOR
MED	MEDIUM
MFR	MANUFACTURER
MH	MANHOLE
MIN	MINIMUM
MISC	MISCELLANEOUS
MR	MOP RECEPTOR
MS	MOP SINK
MTD	MOUNTED

MV	DOMESTIC WATER MIXING VALVE
(N)	NEW
NC	NORMAL CLOSED
NEG	NEGATIVE
NIC	NOT IN CONTRACT
NH	NO HUB
No	NUMBER
NO	NORMALLY OPEN
NOM	NOMINAL
NPW	NON-POTABLE WATER
NTS	NOT TO SCALE
OB	OFF BOTTOM
OC	ON CENTER
OCC	OCCUPIED
OD	OUTSIDE DIMENSION
OD	OVERFLOW DRAIN
OIL	OIL PIPING
OPG	OPENING
OS	OPEN SITE DRAIN
OT	OFF TOP
OX	OXYGEN
PA-SP	PRE-ACTION SPRINKLER MAIN
PART	PARTIAL
PD1	PROCESS DRAIN
PD1V	PROCESS DRAIN VENT
PD2	BATCH RECOVERY DRAIN
PD2V	BATCH RECOVERY DRAIN VENT
PH	PHASE
PIV	POST INDICATOR VALVE
POS	POSITIVE
PRESS	PRESSURE
PRV	PRESSURE REDUCING VALVE
PS	PURE STEAM OR PRESSURE SWITCH
PSG	PURE STEAM GENERATOR
PSI	POUNDS PER SQUARE INCH
PSIG	POUNDS PER SQUARE INCH GAUGE
PSIA	POUNDS PER SQUARE INCH ABSOLUTE
PT	PRESSURE TRANSMITTER
PVC	POLYVINYL CHLORIDE
PW	PROCESS WASTE
PWV	PROCESS WASTE VENT
PWU	PURIFIED WATER UNIT
QUAN	QUANTITY
QD	QUICK DISCONNECT
R	RELIEF PIPING
RAC	RUN ABOVE CEILING
RAD	REFRIGERATED AIR DRYER
RAF	RUN ABOVE FLOOR
RATC	RUN AT CEILING
RBC	RUN BELOW CEILING
RBF	RUN BELOW FLOOR
RBG	RUN BELOW GRADE
RBJ	RUN BETWEEN JOIST
RCP	REINFORCED CONCRETE PIPE
RD	ROOF DRAIN
RD	ROOF DRAIN LEADER
RDM	RUPTURE DISC ALARM MONITOR
REQD	REQUIRED
RHB	ROOF HOSE BIBB
RIC	RUN IN CHASE
RICW	RUN IN CASEWORK
RIE	RUN IN ENCLOSURE
RIW	RISE IN WALL
RM	ROOM
RO	REVERSE OSMOSIS
ROD	ROOF OVERFLOW DRAIN
RPZ	REDUCED PRINCIPLE ZONE
RUD	RUPTURE DISC
RV	RELIEF VALVE
RW	RECLAIM WATER
RWC	RAIN WATER CONDUCTOR
RWH	RAINWATER HARVEST
SS	SANITARY SEWER
S/S	SERVICE SINK
S/SHO	SAFETY SHOWER
SA	SHOCK ABSORBER
SD	STORM DRAIN
SCH	SCHEDULE
SCHEM	SCHEMATIC
SH	SHOWER
SIP	STEAM IN PLACE
SK	SINK
SMP	SUMP PUMP
SP	SPRINKLER MAIN
SPEC	SPECIFICATION

SQ	SQUARE
SRV	SAFETY RELIEF VALVE
SST	SUPPORT STEEL
ST	STORAGE TANK
STD	STANDARD
STL	STEEL
STR	STRUCTURAL
SUP	SUPPLY
SVF	STERILE VENT FILTER
SWC	STERILE WASTE COOLER
SWH	STEAM WATER HEATER
SYS	SYSTEM
T	TANK
TD	TRENCH DRAIN
TD	TECHNOLOGICAL DRAIN
TDV	TECHNOLOGICAL DRAIN VENT
TDH	TOTAL DYNAMIC HEAD
TE	TOP ELEVATION
TEMP	TEMPERATURE
TH	THERMOMETER
TP	TRAP PRIMER PIPE
TPV	TRAP PRIMER VALVE
TPW	PURE WATER STORAGE TANK
T&P	TEMPERATURE & PRESSURE RELIEF
TW	TEMPERED WATER
TYP	TYPICAL
UF	ULTRAFILTER
UG	UNDER GROUND
UH	UNIT HEATER
UNO	UNLESS NOTED OTHERWISE
UNOCC	UNOCCUPIED
UR	URINAL
USPR	USP PURIFIED WATER RETURN
USPS	USP PURIFIED WATER SUPPLY
UV	ULTRAVIOLET STERILIZER
V	VENT
VE	VESSEL
VAC	VACUUM
VI	VIBRATION ISOLATOR
VTR	VENT THRU ROOF
W/	WITH
W/O	WITHOUT
WC	WATER CLOSET
WCO	WALL CLEAN OUT
WDU	WATER DISTILLATION UNIT
WF	WATER FILTER
WFIF	WATER FOR INJECTION FILL
WFIR	WATER FOR INJECTION RETURN
WFIS	WATER FOR INJECTION SUPPLY
WFU	WATER FIXTURE UNIT
WHA	WET STANDPIPE
WH	WATER HEATER
WM	WATER METER
WS	WATER SOFTENER
WSP	WATER HAMMER ARRESTOR

NOTE: NOT ALL SYMBOLS, NOTES, ABBREVIATIONS AND EQUIPMENT ABBREVIATIONS INDICATED APPEAR ON THESE CONTRACT DRAWINGS

VALVE SYMBOLS

- REDUCED PRESSURE BACKFLOW PREVENTER BALL VALVES
- BACKFLOW PREVENTER BALL VALVES
- BACKFLOW PREVENTER O.S.&Y. VALVES

PIPING ELEMENT SYMBOLS

- HB — HOSE BIBB
- ROD — ROOF OVERFLOW DRAIN
- RD — ROOF DRAIN - EXTERIOR
- RD — ROOF DRAIN - INTERIOR
- OS — OPEN SITE DRAIN
- FD — FLOOR DRAIN
- MH — MANHOLE
- CO — CLEANOUT
- WCO — WALL CLEANOUT
- FCO — FLOOR CLEANOUT
- CO — YARD CLEAN OUT OR CLEAN OUT TO GRADE
- PIPE CAP
- LINE BREAK
- 1 1/2" — PIPE SIZE
- UNION - SCREWED OR FLANGED
- SANITARY CONNECTION
- ET — ELECTRICALLY TRACED PIPING
- FILTER
- TD — TRENCH DRAIN
- FIRE HYDRANT
- PIPE RISING UP
- PIPE DROPPING DOWN
- TEE OUTLET UP
- TEE OUTLET DOWN
- PIPE 45° OFFSET DOWN
- CONCENTRIC REDUCER
- ECCENTRIC REDUCER
- PIPE GUIDE
- EXPANSION JOINT
- DIRECTION OF FLOW
- DIRECTION AND GRADE OF SLOPE
- STRAINER
- STRAINER WITH BLOW OFF VALVE
- TB — THRUST BLOCK
- SHOCK ABSORBER
- AQUASTAT
- WATER HAMMER ARRESTOR

FIXTURE SYMBOLS

- UR — URINAL
- WC — WALL MOUNTED, FLUSH VALVE, WATER CLOSET
- WC — FLOOR MOUNTED, FLUSH VALVE, WATER CLOSET
- LAV — LAVATORY
- LAV — LAVATORY
- LAV — LAVATORY
- LAV — WALL MOUNTED LAVATORY
- KS — KITCHEN SINK
- KS — DOUBLE KITCHEN SINK
- EWC — ELECTRIC WATER COOLER
- EWC — SEMI-RECESSED WATER COOLER
- S.SHO — SAFETY SHOWER
- EW — EYEWASH
- S.SHO-EW — SAFETY SHOWER/ EYEWASH
- SHO — SHOWER
- MR — MOP RECEPTOR

REFERENCE SYMBOLS

- X / X — INDICATES DETAIL LETTER (APPLIES ONLY WHERE INDICATED ON DRAWINGS)
- INDICATES DRAWING ON WHICH DETAIL APPEARS
- X — INDICATES TYPICAL DETAIL NUMBER
- INDICATES SECTION NUMBER
- X / X — INDICATES ON WHICH DRAWING SECTION APPEARS
- INDICATES RISER DESIGNATION
- X — X / X — INDICATES SEQUENCE NUMBER
- INDICATES SIZE OF RISER
- X — INDICATES REVISION & NUMBER
- CONNECT NEW TO EXISTING
- POINT OF BEAM PENETRATION
- X — SHEET NOTE NUMBER

GENERAL NOTES

1. REFER TO P&ID LEAD SHEET, CYG011030001 AND CYG011030002 FOR P&ID SYMBOLS, SYSTEM NAMES, LINE CLASSES, VALVES AND ABBREVIATIONS.
2. EXAMINE ALL DRAWINGS RELATING TO WORK OF ALL TRADES AND BECOME FULLY INFORMED AS TO THE EXTENT AND CHARACTER OF THE WORK REQUIRED AND ITS RELATIONSHIP TO ALL OTHER WORK ON THE PROJECT. INSPECT THE SITE AND BE INFORMED WITH RESPECT TO THE CONDITIONS, FACILITIES, DIFFICULTIES AND RESTRICTIONS UNDER WHICH THE WORK SHALL BE DONE. IF DISCREPANCIES IN OR OMISSIONS FROM THE CONTRACT DOCUMENTS ARE FOUND, NOTIFY THE ENGINEER IN WRITING. NO CONSIDERATION OR ALLOWANCE WILL BE GRANTED FOR ANY ALLEGED MISUNDERSTANDING OF MATERIAL TO BE FURNISHED OR WORK TO BE DONE.
3. COORDINATE ALL ACTIVITIES, EQUIPMENT AND UTILITY SHUTDOWNS, WHICH MAY AFFECT ACTIVITIES OF THE BUILDING. COOPERATE WITH THE OWNER TO MINIMIZE DISRUPTIONS TO THE BUILDING'S OCCUPANTS.
4. IT IS THE INTENTION OF THE DRAWINGS TO CALL FOR FINISHED WORK, TESTED AND READY FOR OPERATION. ANY APPARATUS, APPLIANCE, MATERIAL OR WORK NOT INDICATED ON THE DRAWINGS OR ANY INCIDENTAL ACCESSORIES REQUIRED TO MAKE THE WORK COMPLETE TO ALL RESPECTS AND READY FOR OPERATION SHALL BE FURNISHED, DELIVERED AND INSTALLED WITHOUT ADDITIONAL EXPENSE OR TIME TO THE PROJECT.
5. COORDINATE ALL FINAL CONNECTIONS WITH THE OTHER TRADES AND OWNER FURNISHED EQUIPMENT. IF THIS CONTRACTOR INSTALLS HIS WORK BEFORE COORDINATION WITH OTHER TRADES OR THE OWNER SO AS TO CAUSE INTERFERENCE WITH THE WORK OF OTHER TRADES, HE SHALL MAKE ALL NECESSARY CHANGES IN HIS WORK AND CORRECT THE CONDITION WITHOUT EXTRA CHARGE OR SCHEDULE EXTENSION.
6. EACH CONTRACTOR SHALL PROVIDE OPENINGS THROUGH THE CONSTRUCTION AND SLEEVES AS REQUIRED FOR HIS WORK. ANY PIPING OR CONDUIT PASSING THROUGH MASONRY OR CONCRETE WALLS OR FLOORS SHALL BE PROVIDED WITH SLEEVES AS PER THE SPECIFICATIONS. FILL THE ANNULAR VOIDS AS PER THE SPECIFICATIONS.
7. TAKE PRECAUTION AGAINST DAMAGE TO ANY EXISTING UTILITIES, FURNISHINGS AND CONSTRUCTION NOT INCLUDED WITHIN THE SCOPE OF THIS WORK. ANY DAMAGE CAUSED BY THE CONTRACTOR'S OPERATION SHALL BE REPAIRED AT HIS EXPENSE COMPLETE AND TO THE SATISFACTION OF THE OWNER.
8. THE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF THE VARIOUS SYSTEMS AND WORK INDICATED IN THE CONTRACT. THE RIGHT IS RESERVED TO MAKE MINOR CHANGES IN LOCATIONS UP TO THE POINT OF ROUGHING-IN WITHOUT ADDITIONAL CHARGE TO THE OWNER OR SCHEDULE EXTENSION.
9. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SHOW EQUIVALENCE OF ANY PRODUCT SUBSTITUTIONS.
10. WHERE A PRODUCT SUBSTITUTION RESULTS IN RECONFIGURATION OR REWORK OF DESIGN, IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE THOSE CHANGES TO THE ENGINEER FOR APPROVAL.
11. ALL ABANDONED PIPE AND EQUIPMENT SHALL BE REMOVED UNLESS OTHERWISE INDICATED.
12. ALL WORK DESCRIBED IN THESE DOCUMENTS SHALL COMPLY WITH ALL RELEVANT CODES.
13. CLEAN THE JOB SITE CONTINUOUSLY AND REMOVE FROM THE PREMISES ANY DIRT AND DEBRIS CAUSED BY THE PERFORMANCE OF THE WORK INCLUDED IN THIS CONTRACT.
14. MAINTAIN THE INTEGRITY OF ALL EXISTING PIPING SYSTEMS. PRIOR TO CONNECTING NEW WORK TO ANY EXISTING SYSTEM, CONFIRM SYSTEM IDENTIFICATION AND DIRECTION OF FLOW. VERIFY THAT EXISTING PIPING IDENTIFICATION LABELS ARE CORRECT, AND PROVIDE ALL INSTALLATION REQUIREMENTS FOR PROPER CONNECTION TO THE EXISTING SYSTEMS.
15. PROVIDE ALL NECESSARY TEMPORARY OR PERMANENT CAPS, PLUGS, OR BLIND FLANGES FOR PIPING. DO NOT LEAVE PIPING OPEN ENDED.
16. PRIOR TO STARTING CONSTRUCTION, DETERMINE EXACT INVERT ELEVATIONS, SIZE, DEPTH AND LOCATION OF ALL EXISTING UTILITIES WHERE CONNECTIONS ARE TO BE MADE OR INTERSECTIONS OCCUR. WORK BACK TOWARD FIXTURE FROM UTILITY CONNECTION FOR ALL PIPING SYSTEMS.
17. PROVIDE THREE (3) - ELBOW SWING JOINTS FOR ALL HOT WATER BRANCH CONNECTIONS TO THE MAIN.
18. INSTALL ALL SHOCK ABSORBERS IN ACCORDANCE WITH THE LATEST "PLUMBING AND DRAINAGE INSTITUTE" STANDARDS FOR WATER HAMMER ARRESTORS.
19. LOCATE ACCESS PANELS IN NON ACCESSIBLE CEILINGS AND WALLS FOR ALL VALVES, SHOCK ABSORBERS, CLEANOUTS AND ALL OTHER ITEMS THAT REQUIRE ACCESS TO PROPERLY MAINTAIN OR SERVICE THE BUILDING.
20. PROVIDE CLEANOUTS AT THE BASE OF ALL STACKS AND RAINWATER CONDUCTORS. CLEANOUTS SHALL BE LINE SIZE UNLESS OTHERWISE NOTED.
21. ALL VALVES IN THE WATER SUPPLY TO EMERGENCY EYEWASH AND SAFETY SHOWER SHOULD BE LOCKABLE IN THE OPEN POSITION. THE CONTRACTOR SHOULD SUPPLY A LOCK WITH EACH VALVE. ALL OF THESE LOCKS SHOULD HAVE THE SAME KEYING.
22. THE CONTRACTOR SHALL PROVIDE SUPPORTS AND HANGERS FOR ALL NEW PIPING AS SPECIFIED IN SECTION 220529 "HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT", OR ON DRAWINGS. PLEASE REFERENCE SPECIFICATIONS FOR SUPPORT INFORMATION.
23. ALL ELEVATIONS TAKEN FROM FINISHED FLOOR UNLESS OTHERWISE NOTED.
24. IF THE PROJECT INCLUDES ABOVE CEILING AND RAISED ACCESS PLENUM AREAS. ROUTING OF PIPING, DUCTWORK, INSULATION, FLEXIBLE DUCTWORK, WIRING, OR ANY OTHER ITEM THAT IS NOT RATED FOR ABOVE PLENUM AREAS IS PROHIBITED. PLENUM RATED ITEMS SHALL BE USED. THIS REQUIRES A SMOKE DEVELOPED AND FLAME DEVELOPED RATING OF LESS THAN 25/50 PER ASTM AND NFPA. WHERE PIPING OR ELEMENTS ARE USED THAT DO NOT MEET THIS REQUIREMENT, THEY SHALL BE ENCAPSULATED IN SEALED METALLIC PIPING OR WRAPPED WITH CONTINUOUS SEALED FIRE RATED BLANKET.

COPYRIGHT © 2021

NO.	DATE:	REVISION:	APPR:
AW	15OCT2024	G0 - SITE WIDE - IFC	HIPP
AV	10OCT2024	S1 - SHELL - IFC	HIPP
AU	10OCT2024	G1 - ISSUED FOR CONSTRUCTION	HIPP
AT	03OCT2024	S1 - SHELL - IFC	HIPP
AS	03OCT2024	F1 - SHELL - IFC	HIPP
AR	26SEP2024	T1 - ISSUED FOR CONSTRUCTION	HIPP
AQ	23SEP2024	C1 - BULLETIN-0005	HIPP
AP	11SEP2024	F2 - EARLY UG - REVISED	HIPP
AO	11SEP2024	F1 - EARLY UG - REVISED	HIPP
AN	05SEP2024	WH - SHELL - ISSUED FOR REVIEW	HIPP
AM	05SEP2024	F2 - SHELL - ISSUED FOR REVIEW	HIPP
AL	05SEP2024	F1 - SHELL - ISSUED FOR REVIEW	HIPP
AK	26AUG2024	M1 - BASIC DESIGN	HIPP
AJ	26AUG2024	G1 - ISSUED FOR REVIEW	HIPP
AI	22AUG2024	A3 - SHELL - IFC	HIPP
AH	21AUG2024	A2 - SPILL CONTAINMENT - IFC	HIPP
AG	21AUG2024	A1 - SPILL CONTAINMENT - IFC	HIPP
AF	19AUG2024	T4 - ISSUED FOR CONSTRUCTION	HIPP
AE	07AUG2024	S1 - ISSUED FOR FINAL APPROVAL	HIPP
AD	29JUL2024	T1 - ISSUED FOR FINAL REVIEW	HIPP
AC	24JUL2024	T4 - ISSUED FOR FINAL REVIEW	HIPP
AB	18JUL2024	A3 - SHELL - ISSUED FOR REVIEW	HIPP
AA	12JUL2024	T1 - ISSUED FOR FINAL REVIEW	HIPP
Z	12JUL2024	CUB - ISSUED FOR CONSTRUCTION	HIPP
Y	08JUL2024	A2 - SPILL CONTAINMENT	HIPP
X	08JUL2024	A1 - SPILL CONTAINMENT	HIPP
W	26JUN2024	F2 - EARLY UNDERGROUND	HIPP
V	26JUN2024	F1 - EARLY UNDERGROUND	HIPP
U	20JUN2024	T4 - ISSUED FOR APPROVAL	HIPP
T	31MAY2024	A2 - SPILL CONTAINMENT	HIPP
S	31MAY2024	A1 - SPILL CONTAINMENT	HIPP
R	31MAY2024	A2 - SHELL IFC	HIPP
Q	31MAY2024	A1 - SHELL IFC	HIPP
P	09MAY2024	CUB - ISSUED FOR FINAL APPROVAL	HIPP
N	15APR2024	A2 - SHELL SCOPE	HIPP
M	15APR2024	A1 - SHELL SCOPE	HIPP
L	12APR2024	SITE - 100% BASIC DESIGN	HIPP
K	12APR2024	F2 - 100% BASIC DESIGN	HIPP
J	12APR2024	F1 - 100% BASIC DESIGN	HIPP
H	10APR2024	WH - 100% BASIC DESIGN	HIPP
G	04APR2024	SPINE - 100% BASIC DESIGN	HIPP
F	18MAR2024	WWT - ISSUED FOR FINAL APPROVAL	HIPP
E	26FEB2024	CUB - ISSUED FOR FINAL APPROVAL	HIPP
D	23FEB2024	CUB - EARLY UNDERGROUND	HIPP
C	14DEC2023	ISSUED FOR ESTIMATE	HIPP
B	21AUG2023	CONCEPTUAL DESIGN PACKAGE	HIPP
A	28JUN2023	MASTER PLANNING PACKAGE	HIPP

novo nordisk®
Novo Nordisk Pharmaceutical Industries, LP
2641 Powhatan Road
Clayton
North Carolina 27520
USA
Tel. (919)-550-2200

FILL & FINISH EXPANSION
SITE CLAYTON

PLUMBING SYMBOLS AND ABBREVIATIONS

HIPP DESIGN + CONSULTING
2301 REXWOODS DR
SUITE 200
RALEIGH, NC 27607
TEL: 919.755.1033
FAX: 919.755.9995
NC FIRM LICENSE # C-2146
WWW.HIPP-USA.COM

ALL REFERENCES TO "SHELL", "FIT UP", OR OTHER DESCRIPTIONS OF THE SCOPE OF WORK ARE IN SUPPORT OF THE OWNER'S ASSIGNMENT OF CONTRACTS, AS COMMUNICATED TO HIPP DESIGN AND CONSULTING, INC. ANY USER OF THIS CONTENT IS TO CONFIRM ALL SCOPE OF WORK BOUNDARIES WITH OWNER. HIPP MAKES NO REPRESENTATIONS REGARDING THE SCOPE ASSIGNMENT, AND ACCEPTS NO RESPONSIBILITY OR LIABILITY FOR ANY MISREPRESENTATIONS OF SCOPE ASSIGNMENT.

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 045697 ENGINEER A. NEILL
15 Oct 2024

SEAL

PROJECT MANAGER C. JENKINS, P.E.	DEPARTMENT MANAGER K. MANAHER, P.E.
LEAD DESIGN PROF. D. MOORE-HUBBARD, P.E.	CHECKED A. NEILL, P.E.
DRAWN M. PIECHOCKI	DATE 14AUG2023

PROJECT NUMBER
R22034

NNPILP DRAWING NUMBER:
CYG012030000